

E

Quote for Services (Total Lump Sum, Detailed Breakdown Included)-

Delano Village Hall
140 Bridge Ave Delano, MN
Village Hall Parapet Restoration

<i>Job Set Up</i>	Quantity	Units	Price	Cost
Mobilization, insurance expense	1	lump sum	1,975	\$ 1,975
Roof protection	1	lump sum	500	\$ 500
Pedestrian protection/re-trafficking	1	lump sum	800	\$ 800
Scaffolding expense for access	1	lump sum	2,750	\$ 2,750
Final site clean up & dumpster	1	lump sum	950	\$ 950
<i>Work Description</i>				
Remove & salvage cap stones for owner on pallet & plastic wrap	1	lump sum	725	\$ 725
Demo parapet wall & salvage brick for reuse	24	sq ft	38	\$ 912
Rebuild back up wall with new CMU	24	sq ft	45	\$ 1,080
Core fill & re-rod in CMU back up	1	lump sum	750	\$ 750
Rebuild parapet with salvaged brick	24	sq ft	74	\$ 1,776
Sealant installation	8	ln ft	12	\$ 96
Final masonry cleaning	1	lump sum	350	\$ 350

Base Bid Total \$12,664

Alternate Options Available at Additional Costs:

Colum reconstruction	\$2,850	Lump Sum
Capstone reattachment	\$ 450	Each

Exclusions: Permits, roofing, electrical & metal work.

Special Note: Representative scope which we are ready to perform, yet it is subject to change based on the desires of the owner.