

FRONTLINE PLUS, INC.

8004 Aetna Avenue N.E.
 Monticello, MN 55362
 1-800-879-3177-Outstate
 1-763-295-3650-Metro&Fax

QUOTE

Date	
5/10/2010	1143

Name / Address
City Of Delano PO Box 108 Delano,Mn.55328 Attn; A/P

Terms	Due Date	FOB
Net 20 Days.	5/30/2010	Dest/Site

Item	Description	Qty	Cost	Total
VORTEX/R4	<p>This quotation is for one (1) new Siren for the development between Franklin Township and Delano. This proposed unit is a rotating non-voice siren similar to the last 5 sirens Delano has purchased.</p> <p>VORTEX/R4 Electronic Outdoor Warning Siren; 129dBc/100ft, 70dBc/6000ft (Est). 4-400watt speaker drivers, Controls w/Radio receiver for siren set at one-way activation and two-way stand-by. Pole mounting bracket, 50ft cable from siren head to control box. Si-Test Feature. 6-Siren Tones. Activation via DTMF.</p>	1	14,090.00	14,090.00T
BYTEL RAD...	<p>BYTEL RADIO PACKAGE- Consisting of One SMA to Male Adapter, One BWEN Radio Board w/ Motorola CP 200 Radio, Antenna, Polyphaser, 45ft Radio Jumper Cable.</p>	1	1,450.00	1,450.00T

QUOTE ONLY. 60 DAYS Above Date.	Subtotal
	Sales Tax (6.875%)
	Total

E-mail
frontlineplus@tds.net

FRONTLINE PLUS, INC.

8004 Aetna Avenue N.E.
 Monticello, MN 55362
 1-800-879-3177-Outstate
 1-763-295-3650-Metro&Fax

QUOTE

Date	
5/10/2010	1143

Name / Address
City Of Delano PO Box 108 Delano, Mn.55328 Attn; A/P

Terms	Due Date	FOB
Net 20 Days.	5/30/2010	Dest/Site

Item	Description	Qty	Cost	Total
POLE TOP B...	VPTB #01-0411446-00. Pole Top Mounting Bracket.	1	0.00	0.00T
SOLAR PO...	Two (2) 80 Watt Solar Power Panels.	1	3,000.00	3,000.00T
AC Delco DC ...	78-7YR Battery for extended reserve capacities.	2	141.95	283.90T
Installation	Installation: Complete turn-key installation. Includes 55ft wood pole, all required materials, Solar Shutoff as required by NEC and heavy installation equipment.	1	4,500.00	4,500.00T

QUOTE ONLY. 60 DAYS Above Date.	Subtotal	\$23,323.90
	Sales Tax (6.875%)	\$1,603.52
	Total	\$24,927.42

E-mail
frontlineplus@tds.net